BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/21/2017-18 Dated: 06-03-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 15

Name of Work:-Providing chainlink fencing at 4th B cross in B sector of ward No 04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no142, PWD SR 2016-17)	Cum	208.00	90.74	Rupees Ninety and Paise Seventy Four Only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 134 (SR 2016-17)	Cum	208.00	103.58	Rupees One Hundred Three and Paise Fifty Eight Only
3	KSRB-4-1.2 : Providing and laying in position plain cement concrete of mix **1:3:6 withOPC** cement at 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.2/ PWD SR 2016-17	Cum	9.00	5584.11	Rupees Five Thousand Five Hundred Eighty Four and Paise Eleven Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
4	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in **foundation** with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	Sqm	38.40	4633.50	Rupees Four Thousand Six Hundred Thirty Three and Paise Fifty Only
5	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2016-17	Cum	14.40	5538.73	Rupees Five Thousand Five Hundred Thirty Eight and Paise Seventy Three Only
6	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2016-17	Cum	3.60	6275.48	Rupees Six Thousand Two Hundred Seventy Five and Paise Forty Eight Only
7	KSRB 15.1.1: Providing **flush pointing** to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.(Page No.113/Item No. 15.1)	Sqm	64.00	107.34	Rupees One Hundred Seven and Paise Thirty Four Only

	Description	Unit	Approved Qty	Rate Quoted by the Contracto Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
8	Supplying and fixing **M.S Rectangular poles** made out of 2 equal angles of 65x65x6 mm welded together and fixed in cc1;2;4 with 2 nos16 mm dia M,S Hold fasts rods of each length 25 cms, including cost of all materials, cutting,bending scaffolding where ever necessary,nice finishing the welded joints with all lead and as per the direction of the Engineer in charge of the workand including providing 2 coats of approved quality paint over one coat of shop painting(excluding the cost of earth work and concrete) (Page No. 255/ Item No.	Mtr	110.00	906.34	Rupees Nine Hundre Six and Paise Thirty Four Only
9	Providing and fixing **M.S Block pipe of 38 mm dia,** of heavy guage of 14 including the removing the bends,cutting the pipe and fixing the pipe inbetween the two verticle polesM.S Rectangular pole and spot welding the chain linking with M.S Blockpipe including cost of all materials,wastage in cutting and scaffolding where ever necessary with all lead and liftas per the direction of the Engineer in charge of the workand including providing 2 coats of approved quality paint over one coat of shop painting (Page No. 255/ Item No. 37.4)	Mtr	160.00	358.55	Rupees Three Hundred Fifty Eight and Paise Fifty Five Only
10	Providing **chain link fencing 50** mmsize of 8 guage properly stretched bet ween the rectangular poles and fixed with suitable bolts and nuts ,the free ends shall be welded to the pole and block pipe at top and bottom as required , including cost of all materials, labour lead and,liftj and as per the direction of the Engineer in charge of the workand including providing 2 coats of approved quality paint over one coat of shop painting (Page No. 255/ Item No. 37.3)	Sqm	144.00	729.28	Rupees Seven Hundred Twenty Nine and Paise Twenty Eight Only
11	RCC Precast covering slab for drain (10cm thick)	Sqm	56.70	2192.40	Rupees Two Thousand One Hundred Ninety Two and Paise Forty Only

P. Channa Krishna

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP